

**Make sure all penetrations** in the floor cavities are sealed with expanding foam or caulk.



NOTES \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Make sure all supply plumbing** is run close to the conditioned floor or protected with pipe insulation.



**Make sure all mechanicals** are installed as specified, so insulation can be correctly fitted around them.



NOTES \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Make sure the contact points** between the subfloor and band joist and between the rim board and top plate are sealed with foam or caulk.



If **insulating foam sheathing** is specified at the band joist, make sure it's installed and sealed prior to blowing insulation.



NOTES \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Make sure the band joist** is sufficiently insulated.



**Make sure the areas** that can't be adequately filled with blown insulation, such as a bow window, are pre-insulated with batts.



NOTES \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_